

COPY READY FOR
TYPING.

N. PESCE.

SUBJECT: RCRA FAC. INVESTIGATION
#37 POPLAR CREEK DISPOSAL AREA [ACROSS
POPLAR CREEK ALONG RR. TRACKS NE OF K-25]

THE SUBJECT SITE WAS INSPECTED (OCT. 1988)
BY WALKING THE RAILROAD TRACK BETWEEN A
POINT STARTING AT THE SOUTH END OF THE
POPLAR CREEK - RR. BRIDGE CROSSING AND THE
RAILROAD TRACK CROSSING AT THE ACCESS
ROAD TO THE TVA-ROANE SUBSTATION.

THIS RAILROAD TRACK SECTION AND ITS ADJOINING
LAND AREA (EXTENDING AWAY FROM THE TRACKAGE) IS
FOUND CLEAR OF SURFICIAL WASTE AREAS; WITH THE
EXCEPTION OF TWO ISOLATED SPOTS:

- ONE LOCATION IS AT THE RAILROAD TRACK -
SUBSTATION ACCESS ROAD INTERSECTION
WHERE THERE WAS A SMALL PILE OF
DAMAGED/SPLINTERED CREOSOTED RAILTIES.
- THE SECOND LOCATION WAS IN PROXIMITY,
OF THE NORTH END OF THE RAIL TRACK -
POPLAR CREEK CROSSING; WHERE, SEVERAL
RAILTIES REST ALONG THE RAIL TRACK
EMBANKMENT. A SINGLE CONCRETE SECTION
RESTS AT THE TOP OF THE EMBANKMENT.

NO VISIBLE TRASH-SPILL AREAS WERE SEEN ALONG
THE RAIL TRACK BETWEEN THE ROANE SUBSTATION
ACCESS ROAD AND THE BLAIR ROAD CROSSING
OR, ALONG THE RAILROAD SPUR TRACK TO THE
ROANE SUBSTATION.

1] FIGURE 4.4-1 ORGDP WASTE DISPOSAL
SITES

#37 COLIT.

FOLLOWING THE DETERMINATION OF PRESENT SURFACE CONDITIONS, AN INVESTIGATION WAS STARTED TO DEFINE THE USE OF THIS SITE PRIOR TO THE ASSIGNMENT OF THE AREA TO THE CONSTRUCTION OF THE ROANE SUBSTATION. THREE AERIAL PHOTOGRAPHS ²⁾, ATTACHED, PROVIDE EVIDENCE OF PRIOR LAND USE.

INITIAL CONTACTS WITH FORMER K-25 PLANT EMPLOYEES HELPED TO CHARACTERIZE THE PRIOR LAND USE. ³⁾

DURING THE PERIOD OF THE EARLY-MID FORTIES AND THE ADVENT OF THE ROANE SUBSTATION IN 1975-1976 THE AREA HAD BEEN USED FOR SELECT MATERIAL STORAGE OPERATIONS; FOR THE BURIAL OF SELECT NON-COMBUSTABLE BUILDING MATERIALS; AND THE INCINERATION OF COMBUSTABLE MATERIALS. FOLLOWING THE INCINERATION ACTIVITIES THE AREA WAS CLEANED AND GRADED; THEN SEEDED. THESE ACTIVITIES OCCURRED AT DIFFERENT TIMES. NO SPECIFIC TIME PERIODS WERE STATED. WITHOUT HESITATION THE K-25 EMPLOYEES STATED THAT THEY WERE NOT AWARE OF THE DISPOSAL OF ANY HAZARDOUS/CONTAMINATED MATERIALS IN THIS AREA. DURING THE EARLY SEVENTIES THE SITE WAS SHARED USAGE BY TVA AND THE ORGDP OPERATIONS.

2) PHOTOGRAPHS MED-280 [APPROX 1945]
ORO 57-622 [1957]
ORO #586 [SEPT, 1964]

3) FRED MOORE
W. WILLIAMS.





Figure 4.4-1
ORGDP WASTE DISPOSAL SITES




RAILROAD
BRIDGE

TVA
ROANE
SUBSTATION
SITE

ACCESS ROAD
TO
ROANE SUBSTATION


RAILROAD
TRACK

BLAIR ROAD

An aerial photograph showing a landscape with a network of roads and fields. A handwritten label is placed on the image, pointing to a specific location. The label contains the text: "ROANE SUBSTATION", "SITE", and "EAST OF RAILROAD".

ROANE SUBSTATION
SITE
EAST OF RAILROAD

ORO 586



ROANE SUBSTATION
SITE - EAST OF
RAILROAD

NEXT CONTACT WAS INITIATED WITH THE TENNESSEE VALLEY AUTHORITY; WITH THE PURPOSE OF FINDING DATA CONCERNING SITE INVESTIGATION'S CONDUCTED BY TVA IN SUPPORT OF THE SITE SELECTION PROCESS FOR THE ROANE SUBSTATION. A TOTAL OF TVA STAFF PERSONNEL WERE CONTACTED ⁴ THESE CONTACTS PROVIDED VERBAL AND DOCUMENTED INFORMATION. ⁵ THE INFORMATION IS CONSISTENT AND TOTALLY SUPPORTS THE INFORMATION PROVIDED BY THE K-25 EMPLOYEES ⁴ THAT THE ROANE SUBSTATION SITE HAD ONCE BEEN A WASTE DISPOSAL AREA. THE REFERENCED LETTERS ⁵ STATE THAT THERE WAS CONSIDERABLE WASTE MATERIAL LOCATED IN AREAS OF MINIMUM FILL. THE SPOIL INCLUDED WASTE CONCRETE, ASPHALT AND STEEL IN A SOIL MATRIX. NONE OF THE KNOWLEDGEABLE TVA CONTACTS WERE AWARE OF (OR) HAD SEEN EVIDENCE OF THE DISPOSAL OF RADIOACTIVE OR HAZARDOUS MATERIALS.

4 | KNOXVILLE TVA OFFICES

PETER SNEFFLER:

ENVIRONMENTAL COORDINATOR

ROBERT BAIRD

JAMES SULLIVAN

CHATTANOOGA TVA OFFICES

THOMAS NOJTALEK:

ENVIRONMENTAL ENGINEER

JAMES COPP

PHYSICAL PLANNING

WILLIAM FORD

PHYSICAL PLANNING

IT WAS STATED BY THE TVA PERSONNEL THAT, IN PREPARATION OF THE SITE FOR CONSTRUCTION OF THE ROANE SUBSTATION, BURIED WASTE WAS REMOVED AS DEFINED BY DESIGN REQUIREMENTS. HOWEVER NO CONCLUSIVE EVIDENCE WAS GIVEN THAT THE WASTES BURIED OUTSIDE OF THE ROANE SUBSTATION CONFIGURATION HAD BEEN REMOVED.

ONE INTERESTING NOTE WAS OFFERED BY A TVA CONTACT: THE FIRST WATER SUPPLY DEVELOPMENT EFFORTS DID NOT PROVIDE THE REQUIRED WATER QUANTITY AND MORE IMPORTANTLY DID NOT PROVIDE QUALITY WATER. THE WATER CONTAINED E-COLI BACTERIA. EVENTUALLY, QUALITY WATER WAS OBTAINED FROM A WELL LOCATED IN PROXIMITY OF THE FORMER BLAIR ROAD GUARD PORTAL.

CLOSURE:

IT IS NOTED THAT THE TVA PROPERTY LINE EXTENDS BEYOND THE ROANE SUBSTATION AREA. THE PROPERTY IS BOUNDED BY POPLAR CREEK AND BY BLAIR ROAD AS SHOWN ON TVA DWG CW-7064 SH 1 OF 4; "ROANE, TENN. SUBSTATION-PROPERTY MAP."

5/ LETTER: R.C. CRAWFORD TO A.C. PFITZER
JUNE 11, 1976

"ROANE, TENNESSEE, 500-KV SUBSTATION"
SEE ATTACHED

LETTER: G. FARMER TO R.C. CRAWFORD
MAY 12, 1976

"ROANE, TENNESSEE, SUBSTATION 500-KV"
SOIL INVESTIGATION

SEE ATTACHED

#37 CON'T

THE PROPERTY WAS APPROVED FOR ACQUISITION
IN 1976 WITH THE PROPERTY OFFICIALLY
TRANSFERRED ON 7-8-88

THE TVA DOES NOT HAVE ANY PLANS THAT
DEFINE THE BOUNDARY(IES) OF THE BURIED
WASTES. THE SAME IS TRUE OF MMES.
THE TVA RETAINS RESPONSIBILITY FOR
MANAGING THE PROPERTY. CONSEQUENTLY, WE
WOULD EXPECT THAT CHARACTERIZATION OF
ANY RESIDUAL BURIED WASTES WOULD
BE A TVA FUNCTION.

TO : Richard C. Crawford, Chief, Transmission System Siting and Clearance Staff, 523 CBB-C (3)
 FROM : Gene Farmer, Chief, Construction Services Branch, E6B39 C-K
 DATE : May 12, 1976
 SUBJECT: ROANE, TENNESSEE, SUBSTATION 500 kV - SOIL INVESTIGATION

As requested in your memorandum of January 28, 1976, our laboratory has completed the soil investigation for the Roane substation. Sampling and in-situ testing were performed between March 1 and 18, 1976, under generally favorable weather conditions. Borings were drilled with the aid of a trailer-mounted CME 55 drill and hollow stem augers without the use of drilling fluid.

Field Sampling and Testing

Laboratory drawing 604K710 shows the location of 60 standard penetration borings and 1 undisturbed boring. Areas of shaly limestone outcrop and the presence of a large wastefill dump are indicated. The spoil is made up of waste concrete, asphalt, and steel in a soil matrix. A summary of boring data are also tabulated on this drawing.

All borings except those on line 5 were carried to refusal or to a minimum depth of 10 feet. The water table was not encountered during the exploration. Drawings 604B703 through 604K709 show the soil profile established at the site. Overburden depth is quite variable, ranging from 0 to 23.3 feet. Bedrock elevations range from about el. 745 to el. 730 with the highest bedrock elevations occurring at those locations with the highest ground surface. Coring of the shaly limestone in 7 locations along line 5 revealed no major weaknesses with the exception of a 2.7-foot-thick filled cavity in boring SS-B5.

Standard penetration testing disclosed medium to stiff soil consistencies over the site. Standard penetration blow counts usually increase with depth. No particular weakness was established at the soil bedrock contact. Weak zones, N<5 were present at the following locations.

<u>Location</u>	<u>Elevation</u>	<u>N</u>
A3	754	3
D1	748	2
E2	759	3
G1	753	4

RECEIVED
 TRANSMISSION PLANNING
 MAY 13 1976
 TSS & C
 STAFF



Buy U.S. Savings Bonds Regularly on the Payroll Savings Plan

8
A. C. Pfitzer, Acting Chief, Civil Engineering and Design Branch, 202 CEB-C

R. C. Crawford, Chief, Transmission System Siting and Clearance Staff,
323 CEB-C

June 11, 1976

ROANE, TENNESSEE, 500-kV SUBSTATION

Examination of the soil investigation data indicates there is considerable waste material located in areas of minimum fill. This could be of interest to your foundation people since standard penetration tests reveal that there are weak zones present. An undisturbed sample of the waste fill material had an unconfined compressive strength of 0.6 tons/sq. ft.


This project has considerable borrow material at present; therefore, any amount the waste material is undercut will increase the borrow an equivalent amount. Therefore, please examine the attached cross sections and indicate if you need this area undercut giving us any comments that would assist in this matter. Our schedule calls for issuance of the grading plan and related drawings prior to June 21, 1976; therefore, a prompt answer will be appreciated.

JGC:DC

Attachments





KCC



ROANE COUNTY, TENN.
SECOND CIVIL DISTRICT

FIELD BOOK
1-25-27, 28-31
1-30-28
2-7-28

LINE	DESCRIPTION
1	7713.25
2	7713.13
3	7712.98
4	7712.82
5	7712.63
6	7712.43
7	7712.21
8	7711.98
9	7711.74
10	7711.49
11	7711.23
12	7710.96
13	7710.68
14	7710.39
15	7710.09
16	7709.78
17	7709.46
18	7709.13
19	7708.79
20	7708.44
21	7708.09
22	7707.73
23	7707.37
24	7707.00
25	7706.63
26	7706.25



NOTES:
 1. 25' - 70' of E of C of Line Railroad 50' North
 of North-Cor. of Substation. E. 75' 45"
 N. 52' Defeat
 2. 2011 - Ctr. & Chert. Rock Outcrop
 3. CONTOUR MAP - See CN-7064 - Sh. 2-1-28
 RAILROAD RELOCATION - See CN-7064 - Sh. 4
 FLOODING DATA FOR POPULAR CREEK
 FLOOD 100 Year 755.61 755.61
 500 Year 755.61 755.61
 Max. Probable 755.0 755.0
 From Hub #1 to Hub #2 the Substation
 Boundary is a Line 50' from and Parallel
 to the Center Line of Blister Road.
 To Convert TVA Bearings to R.R. Bearings
 Rotate Bearings 0° 55' Lc

Approved for Acquisition (Civil Eng. Department) 1-2-2000

NO.	DATE	DESCRIPTION	BY
17257	1-25-27	Added R.R. Bearings	AKB
17257	1-25-27	Changed Elev. 7713.25 from 7713.13	AKB
17257	1-25-27	Added Mark Order	AKB
17257	1-25-27	Added Station & Access	AKB
17257	1-25-27	Added Property Enclosure	AKB
17257	1-25-27	Core Road Data	AKB
17257	1-25-27	ESTIMATED	AKB

TENNESSEE VALLEY AUTHORITY
 DIVISION OF TRANSMISSION PLANNING AND SURVEYING
ROANE, TENN. SUBSTATION
 PROPERTY MAP
 1-2-2000

ChemRisk Document Request Transmittal Form

(This section to be completed by ChemRisk)

Name S. Sandberg / Division ISD is requested to provide the following document

Address _____

Date of Request 12/10 Expected receipt of document 12/21

Title of requested document ACRA Facility Investigation #37
Poplar Creek...

Document Number 300212

Access Number of Document _____ Date of Document 1976

(This section to be completed by Derivative Classifier)

Derivative Classifier T. G. Jordan Phone 41645

Date document transmitted to Dr. Quist ~~4/15/93~~ 1/29/93

Date release received from Dr. Quist Q82, OK, 1/29/93

PUBLIC RELEASE STAMP attached to each copy of document (YES NO)

Date document sent to reproduction _____ Expected Return _____

Delivered to DRC by _____ Date _____

(This section to be completed by DRC)

Received by DRC _____ Date _____

Processed _____

Mailed _____

1993 FEB -3 PM 5:53

Rec'd KAS CO 1/29/93

Not included in
Area

OAK RIDGE K-25 SITE DOCUMENT RELEASE FORM

C: J Lamb, File, KAS CO-RC (4710)
as 2/1/93

Person requesting release JENNIFER LAMB (CHEMRISK) Telephone No. 4-0745

Mailing Address K-1200 MS-7262 Division or Organization _____

Date by which release is required _____ (Standard processing time is 5 working days.
Some documents require special review and the processing time will be longer).

Note: Two copies of the document must generally be provided to the Classification and Information Control Office with this request. Only one copy of photos and videotapes is required. Documents that include photos must be accompanied by "originals" of the photos.

Approval of request for Classification and Information Control Office to release document (department head or higher):
Signature: _____ Date _____

DOCUMENT DESCRIPTION (to be completed by requester)

Document number UNNUMBERED/300212 Pages 12

Document title RCRA FAC INVESTIGATION #37 POPLAR CREEK DISPOSAL AREA [ACROSS POPLAR CREEK
ALONG RR TRACKS NE OF K-25]

Author(s) (indicate other divisions or organizations, if applicable) N PESCE

Document type (See Doc. Prep. Guide, Chs. 1 and 2, for definitions of document types):

- Formal Report
- Progress Report
- Informal R&D Report
- Abstract
- Drawing
- Administrative
- Correspondence
- Internal Technical Data
- Photo
- Other Visuals
- Journal Article (identify journal): _____
- Oral Presentation (identify meeting, sponsor, location, date): _____

Will oral presentation be published in program, booklet, brochure, etc.? Yes No Not Known

Will copies of the oral presentation be distributed before, after, during the meeting? No distribution will be made.

Other (specify): _____

Purpose of release HEALTH STUDY FEASIBILITY PROJECT

Previously cleared documents containing similar information _____

Is copyrighted material contained in this document? (If present, attach release.) Yes No

Remarks _____

CLASSIFICATION INFORMATION (to be obtained by requester)

Was the work reported in this document funded, in whole or in part, by a classified program at Martin Marietta Energy Systems, Inc.?
 No Yes (Name of program: _____)

Is the subject area of this document closely related to a prior or current classified program at Martin Marietta Energy Systems, Inc.?
 No Yes Within the Department of Energy? No Yes

Name or Description of applicable program(s) _____

Additional remarks _____

This document contains no classified information.

DISTRIBUTION LIMITATIONS (if any) (completed by requester)

Unrestricted, unlimited

Distribution may be limited because this document contains information that is:

Unclassified Controlled Nuclear Information *

Applied Technology *

Export Controlled *

Naval Nuclear Propulsion Information *

Gov't Confidential Commercial Information *

Proprietary

Sensitive Nuclear Technology *

Small Business Innovation Research *

Official Use Only

Safeguards Information *

Cooperative R&D Agreement *

Other

* Generally identified by sponsor

Remarks: _____

PATENT INFORMATION (completed by requester)

Does this document disclose any new equipment, process, or material? Yes No

If yes, list the patent significance and identify page number(s) and line number(s) in the space immediately following (or attach separate pages).

PATENT SECTION ACTION (completed by Patent Section upon request by the Classification and Information Control Office)

Document may be released for publication

Document must be reviewed by DOE Patent Group before release

Document contains patentable information and may not be released at this time

Remarks _____

Patent Section Representative _____ Date _____

CLASSIFICATION AND INFORMATION CONTROL OFFICE ACTION (completed by Classification and Information Control Office)

Classification Office Action Taken: Not approved for release (see below)

Approved for release with changes (see below)

Approved for release without change

Classification Officer signature _____ Date _____

Technical Information Office Action Taken: Not approved for release (see below)

Approved for release with changes (see below)

Approved for release without change

To Chem Desk

Technical Information Officer Signature *Kevin J. Smith* Date *1/29/93*

Send to OSTI? Yes No

Category Distribution: _____

DOCUMENT NUMBER: UNNUMBERED/300212

DOCUMENT TITLE: ROANE, TENNESSEE, SUBSTATION 500 KV - SOIL INVESTIGATION

AUTHORS: G FARMER

DOCUMENT TYPE: CORRESPONDENCE

DOCUMENT DATE: 05-12-76

PURPOSE OF RELEASE: HEALTH STUDY FEASIBILITY REPORT

COPY RIGHTED MATERIAL: NO

APPROVAL FOR RELEASE

Document # Unnumbered (13 pages); Date ND ;

Title/Subject RCRA FAC INVESTIGATION #37 POPLAR
CREEK DISPOSAL AREA [ACROSS POPLAR CREEK
ALONG RR TRACKS NE OF K-25]

Approval for unrestricted release of this document is authorized by the Oak Ridge K-25 Site Classification and Information Control Office, Martin Marietta Energy Systems, Inc., PO Box 2003, Oak Ridge, TN 37831-7307.

Arvin Stewart
K-25 Classification & Information Control Officer

1/29/93
Date